CS656 Ceiling Loudspeaker

www.peas-pa.com



USER MANUAL



Guangzhou Q&S Audio Co., Ltd

Post Code: 510000 Tel: +86-020-66679288 Website: <u>www.peas-pa.com</u>

Address: Room 604, Exchange Center, Panyu, Tian An Hi-tech Ecological Park, Guangzhou, China

Introduction

Thanks for using our speaker products. All our products are tested strictly before leaving the factory, with quaranteed quality.

Our speakers are widely used in such places as schools, gymnasiums, square halls, parks, parking lots, railway stations, airports, villa communities and mall supermarkets, etc., and they will be your ideal choice for public address system.

For better installation, commissioning and use of the product, please read this manual in detail before installation.

Product Features


- 70/100V, 3- 10W with multiple terminals, suited for different field;
- Max. Sound Pressure Level 100±2dB, Effective Freq. Range 130Hz 18kHz;
- Weight 1.0 kg, equipped with clamps for mounting convenient;
- Made of high quality engineering plastic, long-term durability, never out of shape and fade;
- Driver surround excellent damping, provided with high sensitivity (93±2dB), long life, sound clear and sonorousness.

Technical Parameters

Model	CS656
Speaker unit	6.5"×1
Rated power(RMS)	6W
Rated voltage	70V or 100V
Sensitivity(1m,1W)	93±2dB
Max. SPL(1m)	100±2dB
Frequency response	130Hz-18KHz
Dimension	Ф186×70mm
Weight	1.0kg


FREQ. RESPONSE

(dB SPL、1W、1m)




DISTORTION

(THD < 5% 1W, 1m, 100Hz-10kHz)



Installation & Wiring

①. On the ceiling, install a circular hole cut in the 165–170mm a diameter range.







②. Connect audio broadcasting wire to the terminals according to the table below.

Power Voltage Terminals	70V	100V
BlackBlue	3W	6W
BlackWhite	6W	10W

③ Pushing the speakers on both sides of the spring clip up and maintain this status (To avoid spring break, it is recommended that this operation while wearing work gloves), and then let go, push the speakers embedded in the ceiling.





4. finally, check whether the equipment is installed firmly.